



सं०: आई० आई० टी० मण्डी/सी डब्ल्यू/ एस ई-1720/2024-25/2846-47

दिनांक 28-02-2025

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **05-02-2025 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

Name of work: Supplying and fixing of collapsible steel shutter at entry/exit of A11 building towards Arnehar road and closing of open space near staircase with Grill At A9 building, North campus of IIT Mandi.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **30 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt.Orgанизation/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.
11. In case of non-completion of work after the issue of work order, dealers/firms will be debarred for bidding at IIT Mandi for the next one year.

Sd/-
अधीक्षण अभियंता
Superintending Engineer

Copy to:-

1. Notice Board, IIT Mandi.
2. Institute Website, IIT Mandi.

Sd/-
अधीक्षण अभियंता
Superintending Engineer

Schedule of Quantity

Name of the work : Supplying and fixing of collapsible steel shutter at entry/exit of A11 building towards Arnehar road and closing of open space near staircase with Grill At A9 building, North campus of IIT Mandi.

Sr. No.	Description of Item	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per entire satisfaction and direction of Engineer-in-charge	1.00	Sq.m			
2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per entire satisfaction and direction of Engineer-in-charge	222.88	Kg.			
3	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer as per entire satisfaction and direction of Engineer-in-charge	3.19	Sq.m			
4	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters. 80x1.25 mm M.S. laths with 1.25 mm thick top cover as per entire satisfaction and direction of Engineer-in-charge	5.28	Sqm			
5	Providing and fixing ball bearing for rolling shutters as per entire satisfaction and direction of Engineer-in-charge	4.00	No.			
6	Extra for providing grilled rolling shutters manufactured out of 8 mm dia M.S. bar instead of laths as per design approved by Engineer-in-charge, (area of grill to be measured) as per entire satisfaction and direction of Engineer-in-charge	5.50	Sqm			
7	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. <u>Hot finished welded type tubes as per entire satisfaction and direction of Engineer-in-charge</u>	895.09	Kg.			
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : <u>Two or more coats on new work as per entire satisfaction and direction of Engineer-in-charge</u>	37.03	Sq.m			
9	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per entire satisfaction and direction of Engineer-in-charge	5.00	Sq.m			
10	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre. of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. <u>One coat as per entire satisfaction and direction of Engineer-in-charge</u>	5.00	Sq.m			
Total						

Note : 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer