



सं०: आई० आई० टी० मण्डी/सी डब्ल्यू/ एस ई-1735/2024-25/3148-49

दिनांक 06-03-2025

### NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **13-03-2025 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

**Name of work: Providing and fixing aluminium partition and various civil works in academic Block A8 at South Campus of IIT Mandi.**

----- As Per Schedule Attached -----

#### Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **30 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt.Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.
11. In case of non-completion of work after the issue of work order, dealers/firms will be debarred for bidding at IIT Mandi for the next one year.

Sd/-  
अधीक्षण अभिपंता  
Superintending Engineer

Copy to:-

1. Notice Board, IIT Mandi.
2. Institute Website, IIT Mandi.

Sd/-  
अधीक्षण अभिपंता  
Superintending Engineer

**Schedule of Quantity**

**Name of the work :Providing and fixing aluminium partition and various civil works in academic Block A8 at South Campus of IIT Mandi.**

Sr. No.	Description of Item	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead: a. of area 3 sq. metres and below as per entire satisfaction and direction of Engineer -in-charge	1.00	No.			
2	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. a.35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws as per entire satisfaction and direction of Engineer -in-charge	3.00	Sqm			
3	Providing and fixing bright finished brass tower bolts (barrel type) with necessary screws etc. complete : 250x10 mm as per entire satisfaction and direction of Engineer -in-charge	1.00	No.			
4	Providing and fixing bright finished brass 100 mm mortice latch and lock with 6 levers and a pair of lever handles of approved quality with necessary screws etc. complete as per entire satisfaction and direction of Engineer -in-charge	2.00	Nos.			
5	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : a. For fixed portion i.Powder coated aluminium (minimum thickness of powder coating 50 micron) as per entire satisfaction and direction of Engineer -in-charge	233.00	Kg			
6	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately). Powder coated aluminium (minimum thickness of powder coating 50 micron) as per entire satisfaction and direction of Engineer -in-charge	59.00	Kg			
7	Providing and fixing 12mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS:12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. a.Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side.	57.00	Sqm			
8	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound ) content less than 50 gram/ litre, of approved brand and of required shade and colour complete to give and even shade. A.Old work (one or more coats) as per entire satisfaction and direction of Engineer -in-charge	62.00	Sqm			
9	Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C.P brass waste and 40mm C.P. brass trap with necessary C.P. brass unions complete, including painting of fittings and brackets, cutting and making good the wall wherever required : a.Size 600x450x200 mm as per entire satisfaction and direction of Engineer -in-charge	1.00	No.			

Sr. No.	Description of Item	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
10	Providing and fixing uplasticised PVC connection pipe with brass unions : a.45 cm length i.15 mm nominal bore as per entire satisfaction and direction of Engineer -in-charge	2.00	Nos.			
11	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. A.15 mm nominal bore as per entire satisfaction and direction of Engineer -in-charge	2.00	Nos.			
12	Providing and fixing Roller set for aluminium door shutter as per entire satisfaction and direction of engineer- in - charge as per entire satisfaction and direction of Engineer -in-charge	3.00	Nos.			
13	Providing and Fixing 15 mm thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture of size 595 x 595 mm in true horizontal level of approved texture in the grid, including, cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. including repair to exsiting T Runners in wherever required as per specifications, drawings and as directed by Engineer-in-Charge.	38.00	Sqm			
<b>Total</b>						

Note : 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).  
2. All Statutory deduction will be made as per prevailing rates.

Sd/-  
Superintending Engineer